

Noble-Red Clover Creek Project

DESCRIPTION:

Two erosion control rock drop dam structures were built, and fencing was installed on this privately owned section of Red Clover Creek upstream from the Red Clover Demonstration project, which flows into Indian Creek. Willows were planted to hold soil in place.

SPONSORS:

FEDERAL: Agricultural Stabilization and Conservation Service, U.S. Forest Service; PRIVATE: Pacific Gas & Electric Company, Landowner

PROJECT RESULTS:

The dams achieved the objective of slowing the water flow, while the planted willows helped stabilize the stream banks. This project has positively affected 20-30 acres of meadow.

PROJECT REPORTS (IF AVAILABLE):

N/A